

ALICE EMCal Project

T.M. Cormier, WSU

EMCal Project Status

- Project funded as of July 11, 2005 as an pre-conceptual "R&D" project to complete
 - (1) **support structure** design fabrication and installation. Delivery to CERN August 2006. This critical path activity absorbs most of our attention now. See Joseph's talk
 - (2) **test beam prototype detector** design fabrication and test through to mass production readiness.

\$600k received in FY05 out of a total estimated cost for this scope of \$1.6M

EMCal Project Status

Project to be reviewed in December

Scope:

- (1) completion plan for the “pre-conceptual R&D”
Started in FY05. Presentation of our current view of scope / cost / schedule
- (2) Proposed “construction project” consistent with DOE funding profile guidance (FY 07,08,09) = (\$1M,\$2M,\$2M)
- (3) Proposed “construction project” with funding profile optimized to physics scope / schedule and European participation
- (4) Outline of scientific justification

EMCal Project Status

- DOE advice:
Plan for CD-1 by mid summer
- This increases the scope and **cost** of our FY06 R&D activity

EMCal Project Status

Broadening the base

- Actively seeking European (non-US) participation
- First joint US/European meeting on the ALICE EMCal scheduled for beginning of December in CERN
- Meeting participants: French, Italian, Spanish, US, and CERN groups
- Objective: find “first draft” common ground for collaboration consistent various national interests, capabilities and experience

EMCal Project Status

Test Beam

64 tower prototype and test infrastructure nearing completion at WSU

ALICE/PHOS DAQ nearing completion at ORNL@BNL

Fermi Lab meson test beam scheduled for 3 weeks in November

First goal: Preliminary test results (show-and-tell level) ready by DOE review

EMCal Project Status

Project Organization




ALICE-USA Electromagnetic Calorimeter Project Management Plan

Draft 7-12-05

UC Berkeley
UC Davis
UCLA
Creighton University
University of Houston
Kent State University
Lawrence Berkeley National Lab
Lawrence Livermore National Lab
Michigan State University
Oak Ridge National Lab
Ohio State University
Purdue University
University of Tennessee
Vanderbilt University
University of Washington
Wayne State University

(ALICE-USA Collaboration June 2005)

Contents

	I. Introduction	3
	II. ALICE-USA EMCal Project Scope	4
	II.1 R&D Project Scope	5
	II.2 Construction Project Scope	10
	III. ALICE-USA EMCal Project Management	12
	III.2 Project management Responsibilities	12
	III.3 Risk Management Plan	15
	IV. Cost and Schedule	21
	IV.1 Overview of Project Costs	21
	IV.2 TEC Contingency Analysis	22
	IV.3 Schedule and Summary Milestones	25
	Appendix A – EMCal Requirements Document	27
	Appendix B – Level-4 WBS	36
	Appendix C – WBS Dictionary	41

Project Organization: key contacts

James Symons, LBNL NSD Director

T.M. Cormier, Project Manager

Joseph Rasson, Deputy Project Manager

Terry Awes, Electronics, Test Beam

Peter Jacobs, Trigger

Ron Soltz, Computing

Physics Requirements Document

Appendix A ALICE EMCAL REQUIREMENTS DOCUMENT

1. INTRODUCTION

2. EXECUTIVE SUMMARY

- 2.1 Summary Description
- 2.2 Table of EMCal Physical Parameters
- 2.3 Table of EMCal Readout Parameters

3. EMCAL DETECTOR REQUIREMENTS

- 3.1 System Functionality
 - 3.1.1 Measurement Functionality
- 3.2 Calorimeter Characteristics
 - 3.2.1 Energy Resolution
 - 3.2.2 Spatial Resolution
 - 3.2.3 Solid Angle Coverage

4. EMCAL ELECTRONICS

- 4.1 APD Signal Shaping
- 4.2 Dynamic Range of Calorimeter Energy Measurement
- 4.3 EMCal Deadtime

5. EMCAL TRIGGER

- 5.1 Calorimeter Trigger Requirements
- 5.3 Fast Implementation
- 5.4 Trigger Summary Data
- 5.5 Maximum Rates
- 5.6 Input to the High Level Trigger
- 5.7 Latency

6. SLOW CONTROLS

- 6.1 Slow Controls Connection to Detector
- 6.2 Slow Controls Connection to High Level Readout

A Collaboration Document

Prior to DOE Review the Collaboration must conduct a "Requirements Review" by panel of internal and external experts

The Detector

EMCal Concept

Electronics Integration Volume

Super modules:


Two per 20 degree sector

2304 towers per 20 degree sector

Support
Structure

R5400

R4320




EMCal Scope

Baseline Acceptance:


$$\Delta\eta = 1.4$$


$$\Delta\phi = 110^\circ$$

R5400
R4320





EMCal Module = 4 towers






12 Modules combined in
1.5° taper strip module










Strong-back produces
self supporting strip
module


See R&D talk



24 strip Modules per approximately
projective super module

Super Module Integration





Milestones* to First Physics (wish list?)

DOE Review Cost and Schedule Review	1 Jan 06
Final Prototype (Test Beam #2)	1 Aug 06
Support Structure Installation Complete	1 Sep 06
First Super Module on Site	1 Aug 07
First Super Module Ready for Installation	1 Sep 07

*** Pending Funding Approval**